John Day Navigation Lock Monolith Repair

Presented by Matthew D. Hanson, P.E.

Portland District

August 4, 2005



John Day Navigation Lock Catastrophic Failure Prevention and Monolith Repair

Presented by Matthew D. Hanson, P.E.

Portland District

August 4, 2005



JOHN DAY DAM



JOHN DAY NAVIGATION LOCK



Historical

- 1968 Project completed and pool filled.
- Post tension anchors installed in navigation lock gate and tainter valve monoliths (5,6,29,30,27,28,7,8,) as a result of problems at lce Harbor before lock was filled.
- Seepage noted at D/S toe of North embankment (right abutment) 5 days into initial filling @ pool.
- July 1968 structural inspection cited areas of spalling concrete and water flowing down stair treads in the powerhouse gallery.

Historical Cont'd

- March 1969: First Periodic Inspection cited spalling, cracking, inadequate reinforcement
- Subsequent reports indicate increasing amount of cracking, spalling, failed waterstops and leaking.
- Continuous monitoring and repairs on lock monoliths, concrete, etc.
- Waterstop repair contract, tainter valve shaft concrete removal contracts (2001)

Historical Contd'

- Primary Problems necessitating repair (2003)
 - Monolith 8 split in two pieces
 - Monolith 27 in danger of failure
 - Monolith 8 valve shaft spalling and Tainter valve out of service – no operational redundancy
 - Leakage into backfill and boneyard (sinkholes)
 - Monolith movement, cracking, spalling, etc.
 - Customer complaints

Boneyard Sink Hole







Settlement



Monolith 8 Service Gallery – Tainter Valve Shaft










Monolith 8 Service Gallery Concrete Cracking

John Day Lock Crackmeter 1






John Day Navigation Lock – Confirmed Crack Planes




John Day Navigation Lock – Confirmed Crack Planes



Monolith 27 El. 263.0 Service Gallery

John Day Navigation Lock – Concrete Rehabilitation



John Day Monolith Repair Contract Investigation

Stress analysis
Monolith drilling for crack location
Instrumentation/monitoring
Concrete testing
Finite Element Analysis

AND 1. AV 28 2002 15:12:13

John Day Monolith Repair Contract How/Why did this happen?

- •Navigation Lock is not reinforced adequately
- •Concrete strength/quality is variable
- •Foundation is inconsistent and of questionable quality
- •Previous repair measures may have caused cracks which have progressed
- •Waterstop failure due to movement of monoliths allows water into monolith

Monolith Repair - Contract

Lift Joint Repair, Monolith 6&8 Crack Repairs Monolith 8 Structural Repair



Monolith 27 lift joint and Structural Repair

Concrete Removal and Precast Panel Installation



John Day Monolith Repair Construction issues

- •Construction scheduling/considerations of high concern due to lock outage impacts
- •Schedule shift due to Anchor testing
- •Lock outage in march to be extended to 1 month to perform below tailwater drilling
- •12 hour outages above tailwater after outage
- •Best Value contracting method determined in best interest of the Government
- •Critical Contract/Last chance for repair

John Day Navigation Lock Monolith 8


- •Post Tensioning Design
 - •Solid A722 150 ksi Anchors were selected for design.
 - •Anchors were designed to resist the hydrostatic load at 0.6Fy.
 - •An additional 40% increase in required number of bars was then allocated.
 - •In addition, drilling tolerances have been reduced to ½ a degree or within 4" in a 40' deep core.
 - •Tight tolerances will also help prevent hitting existing PT, existing shafts, existing voids, etc.


John Day Navigation Lock Monolith 8

- Anchor Stressing
 - •Every anchor is proof tested to 150% of the design load (0.6Fy).
 - •Several anchors in rock are creep tested to 150% DL for 8 hours.
 - •150% DL is the Corp's single anchor failure criterion. (PTI Criteria 133% DL)
 - •Anchors locked off at 0.6Fu.


John Day Navigation Lock Monolith 8/27


- Anchor Details
 - •Double corrosion protection for anchors installed in rock.
 - •Single corrosion protection for anchors installed in concrete.
 - •Recessed Anchorage zones with tensile zone reinforcement.
 - •Removable anchor caps to allow for retensioning/lift off testing.





e de





John Day Monolith Repair - Construction








John Day Navigation Lock Monolith 27 Post Tensioning Design Cont...:

•New PT was angled and smaller bars were used to eliminate the need to develop bars in the rock strata.

•Fewer monolith penetrations and the no existing PT made the location of these new anchors much less complicated.


•Anchorage details similar to monolith 8 repairs.



John Day Navigation Lock Monolith 27




John Day Navigation Lock Concrete Rehabilitation Monolith Joint Isolation/Sealing •Concrete Repair Monolith 6 Concrete Lift Sealing •Crack Sealing/Repair Backfill Drain Rerouting



Monolith 8/10 Joint Isolation

- 1. Isolate joint from crack to prevent epoxy grout from bonding joint.
- 2. Drill two vertical 10-inch dia access shafts.
- Place expanding chemical "foaming" grout to fill Polyurethane Injection Zone
- 4. Grout Crack.

John Day Navigation Lock – Concrete Rehabilitation



John Day Monolith Repair Contract Joint Sealing Mock-up Testing



Drilled shaft

Simulated monolith joint

Effectiveness of joint filler



Monolith Joint - Paste Epoxy Injection



Monolith joint

Injection Ports ____









Post Tension anchor holes

Epoxy Injection Ports





Monolith Joint

Paste-Epoxy Injection

- Paste-Epoxy injection allows a controlled placement due to a predictable and consistent epoxy distribution "bulb."
- Applicable in a "blind" crack situation

Paste-Epoxy Injection Procedure

- Stage 1 injection until epoxy is observed at 2nd port above.
- 2. Stage 2 injection at intermediate ports.

John Day Navigation Lock Monolith Repair Successes

- Structural Integrity restored
- Normal Lock Operation
- •Leakage to backfill reduced
- •Leakage to lock face reduced
- •Joints/cracks sealed
- •No significant contract claims

John Day Navigation Lock Monolith Repair Costs Original contract estimate \$5.6 million Contract Cost \$11.7 million High cost due to **Tight timeframe Tight Construction Tolerances Work Within an Operating Lock**

John Day Navigation Lock



Portland District Corps of Engineers

Thanks for Listening

Questions?

