Flood Fighting Structures Demonstration And Evaluation Program (FFSD)

#### Tri-Service Infrastructure Systems Conference August 3, 2005



US Army Corps of Engineers



Flood Fighting Structures Demonstration And Evaluation Program (FFSD)

- 1. Background
- 2. Product Selections
- 3. Laboratory Testing
- 4. Field Testing
- 5. Product Summaries
- 6. Remaining Work



US Army Corps of Engineers ERDC

# Flood Fighting Structures Demonstration And Evaluation Program (FFSD) Authorization

**2004 Energy and Water Development Bill** 

"The conferees therefore direct the Corps of Engineers to act immediately to devise real world testing procedures for Rapid Deployment Flood Wall (RDFW) and other promising alternative flood fighting technologies."



US Army Corps of Engineers



# **Product Selections** Congressional Directive Rapid Deployment Flood Wall (RDFW)





US Army Corps of Engineers



# Product Selections Standard for Comparison Sandbags





US Army Corps of Engineers



# **Product Selections**

- 1. Develop Evaluation / Selection Criteria
- 2. Issue Solicitation for Technical Proposals
  - 9 Proposals Received
  - Categories Product Type
  - Impermeable Liner (with or without frame)
  - **Granular Filled Container**
  - **Water Filled Bladder**
- 3. Evaluate Proposals and Make Selections Based on Technical Merit



US Army Corps of Engineers

ERDC

# **Product Selections** Competitive Technical Proposals Portadam





US Army Corps of Engineers



# Product Selections Competitive Technical Proposals Hesco Bastion







US Army Corps of Engineers



### **Evaluation Parameters**

**1. Product Requirements Footprint and ROW requirements Durability** Ease of Construction and Removal **Time / Manpower/ Equipment** Adaptability to Varying Terrain Seepage **Fill Requirements** Cost **Repair and Reusability Ability to Raise During Flood** 

2. Tests

Static Loading Overtopping Wave Impact Debris Impact

3. Performance on Various Surfaces Freshly Graded Grass / Weeds Finished Concrete




US Army Corps of Engineers

ERDC

# Laboratory Testing

# Construction Footprint





US Army Corps of Engineers

ERDC

# **Laboratory Testing**



#### Sandbag Structure

#### **RDFW**





US Army Corps of Engineers



# Laboratory Testing Debris Impact







US Army Corps of Engineers



### **Laboratory Results**


<u>Structure</u>	Construction Effort <u>(man hours)</u>	Removal Effort (man hours)
Portadam	24.4	4.4
Hesco	20.8	13.4
Sandbags	205.1	9.0
RDFW	32.8	42.0

ERDC



US Army Corps of Engineers

## Laboratory Results Seepage



US Army Corps of Engineers

ERDC

### **Laboratory Results - Damage**

Sandbag Structure Repeatedly damaged by waves Failed during overtopping

#### **Hesco-Bastion**

Minor sand settling and washout Wire bent during debris impact tests







US Army Corps of Engineers



### **Laboratory Results - Damage**

#### **RDFW**

Minor sand settling Significant washout along edges and toe Toe damaged during large waves or overtopping 10% of structure broken

#### Portadam Liner torn during debris impact test







US Army Corps of Engineers ERDC

### **Field Testing** Site Selection





US Army Corps of Engineers



#### **Field Testing** As Constructed





US Army Corps of Engineers



### **Portadam – As Delivered**







US Army Corps of Engineers



# **Portadam Structure**







US Army Corps of Engineers



#### **Hesco Bastion – As Delivered**





US Army Corps of Engineers



# **Hesco Bastion Structure**





US Army Corps of Engineers



## Hesco Bastion Installation Modification







US Army Corps of Engineers



# **Sandbag Structure**





US Army Corps of Engineers

ERDC

### **RDFW – As Delivered**





US Army Corps of Engineers



# **RDFW Structure**





US Army Corps of Engineers



# **RDFW** Post Testing Modifications





- Color Coded for Accurate Installation
- Rounded Corners



Suction Trailer Available to Expedite Removal

US Army Corps of Engineers

ERDC

### Field Testing Construction and Removal


	Construction		Re	Removal	
<u>Structure</u>	Time <u>(hours)</u>	Effort <u>(man hours)</u>	Time <u>(hours)</u>	Effort <u>(man hours)</u>	
Portadam	5.1	26.2	2.9	12.6	
Hesco Bastion	8.9	57.5	8.7	36.3	
Sandbags	30.5	453.1	2.6	3.5	
RDFW	7.5	48.4	17.3	113.4	

ERDC



US Army Corps of Engineers

# Field Testing Seepage



ERDC

US Army Corps of Engineers

# **Field Testing - Damage**

#### Portadam

None - 100% reusable

#### **Hesco Bastion**

Bent some panels and coils Over 95% reusable

#### Sandbags

Bags began to deteriorate All sandbags disposed

#### **RDFW**

Broke some unit pieces 95% of pieces reusable







US Army Corps of Engineers

ERDC

**Portadam Summary Strengths Ease of Construction / Removal** (time, manpower, equipment) Low seepage rates No fill required High degree of reusability Least ROW required Weaknesses Punctured during debris impact test Can't be raised in typical application



US Army Corps of Engineers ERDC

**Hesco Bastion Summary Strengths** Ease of Construction / Removal (time & manpower) Low cost High degree of reusability Can be raised Weaknesses Significant ROW required due to granular fill **Highest seepage rates** 



US Army Corps of Engineers



#### **Sandbag Summary**

Strengths Low Cost (volunteer / prison labor) Conforms well to varying terrain Low seepage rates Can be raised

> Weaknesses Very labor intensive Not reusable



US Army Corps of Engineers



**RDFW Summary Strengths** Ease of Construction (time & manpower) Low seepage rates High degree of reusability Can be raised Most height flexibility (8 inch units) Weaknesses Significant ROW required due to granular fill High cost **Difficult to remove** 

US Army Corps of Engineers ERDC

# **Remaining Work**

- 1. Place testing data and results on publicly accessible web page.
- 2. Conduct pilot tests at 3 locations around the country. Philadelphia / Baltimore Districts Omaha District Sacramento District
- 3. Use purchased products in actual flood events.



US Army Corps of Engineers ERDC

### Pilot Testing Omaha District - Missouri River





#### As Installed



#### **July 2005**



US Army Corps of Engineers



### Use During Actual Flood Iron County, Utah







Removal July 2005



US Army Corps of Engineers

Installation

May 2005



#### Flood Fighting Structures Demonstration And Evaluation Program (FFSD)





US Army Corps of Engineers



### **Contact Information**

**Fred Pinkard** 

(601) 634-3086

U.S. Army Corps of Engineers Engineering Research and Development Center Coastal and Hydraulics Lab Vicksburg, MS

Fred.Pinkard@erdc.usace.army.mil



US Army Corps of Engineers ERDC